

VILLAGE OF ROCKVILLE CENTRE

ONE COLLEGE PLACE, P.O. BOX 950

ROCKVILLE CENTRE, N.Y. 11571-0950



FRANCIS X. MURRAY, MAYOR
KATHLEEN BAXLEY, TRUSTEE
MICHAEL SEPE, TRUSTEE
EMILIO F. GRILLO, TRUSTEE
KATIE CONLON - TRUSTEE

PURCHASING DEPARTMENT

516/678-9213

4/25/2023

Veteran's Park Lighting Infrastructure

Bid No. 2305E4(1074)

Addendum No. 1

Questions asked of the Village:

Question # 1: Item 601 P 2-2 Plan calls for schedule 40 pipe bid sheet has schedule 80 please clarify.

Answer: All piping to be sch. 80 throughout project. (see attached drawing with revised legend)

Question # 2: Item 602B Quanzite pull box Depth of trench at 24" box at 18 inches terminate pipe at box with a 45 or 90 into box.

Answer: Yes. The contractors are to provide an elbow (45 or 90) into the box to terminate above earth at bottom of box. This will be typical at each "Quanzite" box connection.

Question # 3: Caution tape placed on all pipe

Answer: Yes. Contractor is to install electric caution tape at all piping prior to backfilling. (no separate pay item for this work)

End of Addendum No. 1

Please return this signed Addendum with your bid response.

Company: _____

Signature: _____

Date: _____